## Material Passports

SEDA Meeting of Minds 02.09.2022





































1	Group Element	Element	Description	Material Arising			SW 8	li e	Total Control	16	Cost to remove/process			Cos	- avoided impacts	Carbon - avoided impacts				
Item Ref				Qty	Unit	%ge recoverable	Waste Recovery Commentary	Waste Route Commentary	Waste Route		Sum	Comments		Sum or new)	Comments	Carbon (kgCO2e/t)	Carbon (kgCO2e)	Cart (£/tC		Comments
111	Substructure	Strip foundations	In situ concrete formed with rebar cages	96	m3	100%	Grub up and crush to provide aggregate elsewhere. Assume stored on site.	Aggregate for use as back-fill. Re-bar may be an issue.	3	£	19,200	Rate for labour items, assumed crusher brought onto site (see preliminaries)	£	2,880	Meterial only; excludes movement around site	103	23,731	£		General average embodied carbon rate applied to Concrete embodied carbon = 103kgCO2 x mass (f) Reber weight factor = 0.100t of reber per m* concrete. 648 x 0.1 = 64.8t Reber embodied carbon = 1200kgCO2/t = 77,760kgCO2
11.2	Substructure	Ground floor slab	In-situ RC slabs poured between ground beams.	135	m3	100%	Grub up and crush to provide aggregate elsewhere. Assume stored on site.	Aggregate for use as back-fill. Re-bar may be an issue.	3	£	27,000	Rate for labour items, assumed crusher brought onto site (see preliminaries)	£	4,050	Material only; excludes movement around site	103	33,372	£		Concrete embodied carbon = 103kgCO2 x mass (T) Reber weight = 27t Reber embodied carbon = 32,400kgCO2
1.1.3	Substructure	Damp-proofing/tanking	Assume a slurry beneath the slab and founds.	225	mZ	0%	Assume unrecoverable.		4	£	58	Assumed strip out and dispose	£	5 <del>5</del>			2.5%	£	7.50	
11.4	Substructure	Sack-fill/hardcore	Assume graded and compacted hardcore backfill beneath slab/foundations.	259	m3	100%	Assume dug up, washed and graded.	Sold or set eside for re-use.	3	£	12,960	Assumed reused on the same site, or collected by buyer if sold	£	7,776	Material only; excludes movement around site	7.5	2,916	£	108	General UK aggregate mix
2.1.3	Superstructure	Upper floor slabs	Pre-cast concrete slabs fixed to loadbearing panels.	405	m3	100%	Cut re-bar connection to surrounding structure. Make good cut ends to prevent corrosion.	Use as sub-base for new external paved areas.	1	E	101,250	Assumes broken down into easily manoeuvrable component sizes	£	40,500	Material only; excludes movement around site	103	100,116	£		Concrete embodied carbon = 103kgCO2 x mass {T} Rebar weight = 3.7t Rebar embodied carbon = 4.440kgCO2
214	Superstructure	Loadbearing internal walls	Pre-cast Mitchell Camus panels.	287	m3	100%	Cut re-bar connection to surrounding structure. Make good cut ends to prevent corrosion.	Aggregate for use as back-fill. Re-bar may be an issue.	3	£	71,712	Assumes broken down into easily manoeuvrable component sizes	£	28,685	Material only; excludes movement around site	136	93,627	£		Assumed RC in situ 28/33  Mpa concrete used  Concrete embodied carbon = 136 x mass (T)  Rebar CO2 = 95.640kgCO2
2.1.5	Superstructure	External walls - original ground floor	Pre-cast concrete Mitchell Camus system.	474	m2	100%	Cut connections to the frame and treat all exposed steel leaving ready for re-use elsewhere.	U values don't meet modern construction without additional insulation. However no reason these panels should not be used on new buildings as part of a broader system.	1	£	18,960	Assumes fixings are in good condition and can be reused without any repair work	£	47,400	Based on precast wall panels; dependent on specification; excludes costs associated with fitting old system vs new	136	23,207	Ē	860	Assumed RC in situ 28/33 Mps concrete used Concrete embodied carbon = 136 x mass (T)
2.1.6	Superstructure	External walls - original upper floors	Pre-cast concrete Mitchell Camus system.	1422	m2	100%	Cut connections to the frame and treat all exposed steel leaving ready for re-use	U values don't meet modern construction without additional insulation.	1	£	56,880	Assumes fixings are in good condition and can be reused without any repair work	£	142,200	Based on precast wall panels; dependent on specification; excludes costs	178	91,122	£	2000000	Precast concrete embodied cerbon = 178kgCO2 x mass (T)









The Circle

5.200

54,000

